

## Maine Conservation Corps

124 State House Station, Augusta, ME 04333-0124

Ph: 207/287-4931 Fax: 207/287-3342

Ph: (in Maine only) 800/245-5627

e-mail: [corps.conservation@maine.gov](mailto:corps.conservation@maine.gov)

November 21, 2005

Fred Grey  
1315 Blue Mount Road  
Monkton MD 21111-1229

Dear Fred:

Thank you for inviting me to assess the trail conditions on Monhegan Island. I have enclosed a spreadsheet that estimates the time and materials that would be required to rehabilitate all deficiencies we observed on the trails. The list is a long one, but it is all-inclusive and should give you the ability to set priorities and plan for improvements for a long time.

I have also included a map of the GPS tracks I made – in case you want to update your maps.

### Notes and observations:

 Here is my sense of priorities after visiting all the trails on the Island.

- Any where in the log where it calls for a water bar should be a priority. Diverting water soon will have a very beneficial effect and help prevent further degradation.
- Lobster Cove and the hillside near the Wyeth home. This area sees many visitors, and would do well to receive some attention – both the eroded footpath(s), the open areas used by artists, and the numerous trails to the shore.
- Little Whitehead – the steep slope on the south side of the headland where footing is poor and getting worse.
- Install stone steps and waterbars on Whitehead – steep slopes on all three sides of the headland.
- Rehabilitate the steep hill descending to Pebble Beach – probably a mix of relocation and stone steps.

 The largest category of needed work is building stone steps to harden trails, prevent erosion and improve footing and safety for visitors – the trail log shows a need for over 1600 steps throughout the trail system, which represents over 70 weeks of MCC team time. Some sites are less at risk for degradation, and you might choose to delay action in these places. I think MCC can help you the most in this type of work since it requires special skills, tools and techniques. This work is much less likely to be done by local volunteers.

- 🌐 If you develop a proposal to utilize MCC, you can plan on 1 team week being 240 hours (including transportation). It is also helpful to group projects in certain areas, so as to avoid lost time moving around with tools and equipment.
- 🌐 Bog bridging can be used in any areas where wet ground or flooding is an inconvenience to hikers. Wet and trampled areas are quick to recover once bridges are installed, so this work is easier to delay.
- 🌐 I found the trails to be clear and easy to walk. My only suggestion is to consider using larger number signs at important trail junctions, and to develop some type of intermediate marking along the trails to assure that strangers are comfortable finding their way around.
- 🌐 The log shows distance in feet along every segment we walked. I have not tried to calculate and trail distances. I think you are better equipped to decide which distances you would like, and make calculations with fewer errors than I might.

Thank you for your hospitality on Monhegan, and your guiding me around the trails. I believe I started to gain some insight into the special nature of Monhegan Island.

Please let me know if I can be of further assistance.

Sincerely,

Lester C. Kenway  
Maine Conservation Corps

**Trail Log - Monhegan Trails - LC Kenway 10/12-13-14/05**

**3 hours on Sunday  
2 hours on Monday**

<b>Feet</b>	<b>GPS Description</b>	<b>Project</b>	<b>MCC Hours</b>
0 003	Jct Ice Pond Rd/Black Head Road		
1276	Jct Cathedral Woods #11		
	<b>Follow #11 East</b>		
1313	Sign - "please help us. . . "		
1512	False Trail to right to canal		
1722	Start Puddle		
1743	End Puddle at ledge	Install 3 bog bridges	20
1819	Puddle		
1931	Start need Bog Bridge		
1949	End need Bog Bridge	Install 3 bog bridges	20
2003	Start Bridge		
2020	End Bridge - replace w/in 5 years		
2105	Open area brush in/rehab		
	<b>Need Fairy House guidelines</b>		
2359	Need waterbar	Build waterbar	12
2498	Need waterbar	Build waterbar	12
2584	Start need Bog Bridge		
2639	End need Bog Bridge	Install 7 bog bridges	50
2667	Jct #12 Long Swamp Trail		
	<b>Continue East on #11</b>		
2722	Start need Bog Bridge		
2757	End need Bog Bridge	Install 5 bog bridges	40
2955	Start need Bog Bridge		
2993	End need Bog Bridge	Install 5 bog bridges	40
3058	Jct #16 Maple Trail		
	<b>Continue East on #11</b>		
3068	Start need Bog Bridge		
3100	End need Bog Bridge	Install 4 bog bridges	30
	Possible relocation around ledge		
3222	Start need Bog Bridge		
3246	End need Bog Bridge	Install 3 bog bridges	30
3293	Start need Bog Bridge		
3358	End need Bog Bridge	Install 8 bog bridges	56
3410	Start need Bog Bridge		
3484	End need Bog Bridge	Install 9 bog bridges	60
3484	Jct 1A connector		
	<b>Continue East on #11</b>		
3624	Start need Bog Bridge		
3690	End need Bog Bridge	Install 9 bog bridges	60
3777	Start need Bog Bridge		
3828	End need Bog Bridge	Install 7 bog bridges	50
3869	Start need Bog Bridge		
3943	End need Bog Bridge	Install 9 bog bridges	60
3935	Jct Trail #1 near Squeaker Cove		
	<b>Go Northeast on #1</b>		
4005	Start ledges		
4078	Optional route to North		
4196	Rejoin optional route		

4197	Need 2 bog bridges	Install 2 bog bridges	16
4270	Step stones - need 8	Install 8 stepping stones	80
4496	<b>Paint Marks on stones may be helpful</b>		
4887	Rock Steps - need 10	Build 10 stone steps	100
5056	Boulder Gulley		
4093	Rock Steps - need 14	Build 14 stone steps	140
	Rock Steps - need 30	Build 30 stone steps	300
	Difficult work		
5226 005	Jct #10, #1A near BlackHead		
	<b>Return to Jct #11 and 1, GO SW on #1</b>		
5989	Cross stream, need Bog Bridge	Install 1 bog bridges	8
6033	False Trail to cove		
6072	Rock Steps - need 45	Build 45 stone steps	450
6303	<b>Jct #1 and 1A, go on #1 SW</b>		
	Step stones - need 20	Build 20 stone steps	200
6533	Rock Steps - need 40	Build 40 stone steps	400
6597 006	<b>Jct #1 and 1A, go on #1A NE</b>		
6780 007	Jct Connector to 11(cont. on 1A)		
6843	Rock Steps - need 14	Build 14 stone steps	140
6948	Steep rocks		
6980	Start need Bog Bridge		
7052	End need Bog Bridge	Install 9 bog bridges	70
7072	Jct #1		
7079	<b>Start Connector to #11 near Squeaker</b>		
7273	Jct #11 - need 10 ft bog bridge	Install 2 bog bridges	16
7657	<b>Start #1 SW at Jct 1A near Little Whitehead</b>		
7720	False Trail		
7797	False Trail		
7896	Little Whitehead		
7939 008	Jct #1/#1A		
	<b>Go NE on #1A</b>		
8134	Start #1A		
8150	Rock Steps - need 66	Build 66 stone steps	660
	<b>Going down steep slope on Little Whitehead</b>		
8262	Bottom of slope		
8411	False Trail		
8487	False Trail		
8612	Short, steep ledge		
8632	False Trail		
8684	False Trail		
	<b>Note effect of shearing spruce trees</b>		
8685 009	Jct #12 Long Swamp Trail		
	<b>Take #12 Northwest</b>		
8811	Start need Bog Bridge		
8831	End need Bog Bridge	Install 3 bog bridges	24
9033	Start need Bog Bridge		
9081 010	<b>Jct #12 &amp; 1A - Take 1A Southwest</b>		
9082	End need Bog Bridge	Install 6 bog bridges	48
9230	Stream Crossing w/ 50 step stones		
9460	Start need Bog Bridge		
9511	End need Bog Bridge	Install 7 bog bridges	56
9536	Rock steps - need 20	Build 20 stone steps	200

9625	Need 2 bog bridges or relocate	Install 2 bog bridges	16
9801	Need 10 step stones	Install 10 stepping stones	100
10127 011	Jct Whitehead Trail #7		
	<b>Go NE up Whitehead #7</b>		
10203	Need waterbar	Build waterbar	12
10246	Need waterbar	Build waterbar	12
10284	Need waterbar	Build waterbar	12
10327	Need waterbar	Build waterbar	12
10371	Need waterbar	Build waterbar	12
10559	Need 22 steps or step stones	Install 22 stepping stones	220
10689	Start need Bog Bridge		
10715	End need Bog Bridge	Install 4 bog bridges	32
10770 012	Jct #7 and #1 on Whitehead		
	<b>Go NE on #1</b>		
10840	Eyebolt on Whitehead		
11246	Start Log or rock Checks	Install 6 checks	50
11280	End Log or rock Checks		
11311	Rock Steps - need 30 (rocks?)	Build 30 stone steps	300
11386	Rock Steps - need 40	Build 40 stone steps	400
	Waterbars - need 6	Build 6 waterbars	70
11583	<b>Jct connector to 1A - Cont NE on #1</b>		
11602	Stream Crossing		
11707	Jct #12		
12305	<b>Resume Notes at #12/#1A, Go North on 12</b>		
12813	Start need Bog Bridge		
12839	End need Bog Bridge	Install 4 bog bridges	32
13126	Need 2 bog bridges	Install 2 bog bridges	16
13174 015	Jct #11/#12		
	<b>Go along 11 as far as #16</b>		
13555	<b>Jct #16, go N on #16</b>		
13888	Start need Bog Bridge		
13991	End need Bog Bridge	Install 13 bog bridges	100
14027	Start need Bog Bridge		
14181	End need Bog Bridge	Install 20 bog bridges	150
14181	Start need Bog Bridge		
14224	End need Bog Bridge	Install 6 bog bridges	40
13372	Need to begin ditch and drain	Dig 50 feet of side drainage	6
14420	Need to end ditch and drain		
14709 017	Jct #10, middle of Island		
	<b>Resume tour on 10/13/05</b>		
0 018	Start trail #7 at Ballfield		
247	False trail to left		
312	Top of small hill before descent (photo)		
370	Need waterbar	Build waterbar	12
437	Need waterbar	Build waterbar	12
500	Exposed ledge		
	Need 20 steps	Build 20 stone steps	200
600	Need waterbar	Build waterbar	12
691 019	Jct Trail #6		
746 020	Jct Trail #9		
840	Start section with wood chips		
881	End section with wood chips		

1069	False trail		
1131	Need start bog bridges		
1187	End bog bridges	Install 7 bog bridges	56
1251 011	Jct Trail 1A to left		
	<b>Go To Start of Trail #9</b>		
1358 020	Start trail #9		
	Possible 80 ft of bog bridge	Install 10 bog bridges	80
1498	Start need Bog Bridge		
1515	End need Bog Bridge	Install 2 bog bridges	16
2270	Start need Bog Bridge		
2287	End need Bog Bridge	Install 2 bog bridges	16
2806	Start need Bog Bridge		
2850	End need Bog Bridge	Install 6 bog bridges	48
2978	Footbridge -		
3006	replace w/in 5 years		
3358	Start need Bog Bridge		
3385	End need Bog Bridge	Install 4 bog bridges	32
3677	Start need Bog Bridge		
3718	End need Bog Bridge	Install 5 bog bridges	40
021	Jct Trail #9 with Trail #10		
	<b>Follow Trail 10 towards Blackhead</b>		
6502	Jct Trail #16		
6632 022	Jct. Trail #17		
7019 023	End of vehicle travel		
7310	Need drainage ditch	Dig drainage ditch	6
7489	False trail near firebox		
7573	Start need Bog Bridge		
7594	End need Bog Bridge	Install 3 bog bridges	24
7612 015	Jct Trail #1		
	<b>Go towards Blackhead</b>		
7895 024	Jct 1A and 1		
	<b>Follow Trail 1 north</b>		
7946	False Trail		
8032	False Trail		
8429	Need 12 stone steps	Build 12 stone steps	120
8444	End rock steps		
8504 025	Jct 1 and 1A near pulpet rock		
	<b>Follow Trail 1A south</b>		
8578	Rock bridge (photo)		
9289	False Trail (photo)		
9302	False Trail		
9472	False Trail		
9523 024	Jct 1A and 1		
	<b>Return to Jct 1 and 1A (025)</b>		
10144	Jct 1A and 1		
	<b>Follow Trail 1 north</b>		
10144	Retaining wall		
10369	Need drainage ditch	Dig drainage ditch	6
10753 026	Jct Trail #18		
	<b>Continue Trail 1 north</b>		
10791	Need 3 step stones in stream	Install 3 stepping stones	30
10889	Need 24 stone steps	Build 24 stone steps	240

10925	End steps		
11033	Many trails		
11293	Rock gully		
11534	Need 18 stone steps	Build 18 stone steps	180
11598	Need 12 stone steps	Build 12 stone steps	120
11701	Need 20 steps	Build 20 stone steps	200
11726	False Trail		
11831	Need 18 stone steps - stream/ledge	Build 18 stone steps	180
11973	Rock channel		
12015	Need start bog bridges		
12040	End need Bog Bridge	Install 2 bog bridges	16
12150	False Trail		
12186	Need 20 stone steps	Build 20 stone steps	200
12282	Need 6 step stones	Install 6 stepping stones	60
12314	Need 20 stone steps	Build 20 stone steps	200
12599	Need 36 stone steps	Build 36 stone steps	36
12657 027	Jct Trail #1 and #17		
	<b>Follow Trail 17 south</b>		
	Need 3 bog bridges	Install 3 bog bridges	24
12808	Need 24 stone steps	Build 24 stone steps	240
12939	Need 26 stone steps	Build 26 stone steps	260
12939	Need start bog bridges		
13023	End need Bog Bridge	Install 11 bog bridges	88
13048	False trail steep bank		
13435	Remove stump, 6 steps	Remove stumps and build	
13522	Need start bog bridges	6 stone steps	60
13601	End need Bog Bridge	Install 10 bog bridges	100
13726	Need start bog bridges		
13806	End need Bog Bridge	Install 10 bog bridges	100
13836 028	Jct #17 and #18		
	<b>Follow #18 west over Station Hill</b>		
14160 029	Suvery Marker		
14423	Need 24 stone steps	Build 24 stone steps	240
14703	Need 16 stone steps	Build 16 stone steps	160
14760	Need start bog bridges		
14774	End need Bog Bridge	Install 2 bog bridges	16
14876	Jct #18 and #1 on shore		
	<b>Walk back along #18</b>		
	<b>Resume #17</b>		
14962 028	Start need Bog Bridge		
15291	End need Bog Bridge (possible relocation)	Install 40 bog bridges	300
15528 022	Jct Trail #17 and #10		
	<b>Return to Village</b>		
0 030	Jct #1 and #10, north of village		
	<b>Follow Trail #14 towards pebble beach</b>		
114	Jct curator cottage		
157 031	Jct Trail #1 and #14		
325	Need 5 step stones	Install 5 stepping stones	50
	Need 30 stone steps	Build 30 stone steps	300
790	Need 3 bog bridges	Install 3 bog bridges	24
944	Start need Bog Bridge		

986	End need Bog Bridge	Install 6 bog bridges	48
1716	Viewpoint		
1745	Need 2 steps (photo source area)	Build 2 stone steps	20
1871	Need 4 checks (photo)	Build 4 checks	30
1993	Need 80 stone steps	Build 80 stone steps	800
	Need 3 waterbars	Build 3 waterbars	36
2188	Need 25 stone steps	Build 25 stone steps	250
2301	Need 2 waterbars - possible relocation	Build 2 waterbars	24
	Need 17 stone steps	Build 17 stone steps	170
2327 032	Jct Trail #1 and Trail #14		
	<b>Follow Trail #1 NE</b>		
2581	Water in trail		
2643	Need step stones or relocation		
2723	Need 30 stone steps	Build 30 stone steps	300
2973 033	Jct Trail #1 and Trail #15 near house		
	<b>Continue Trail 1 northeast</b>		
3273	Need 40 stone steps - Relocation?	Build 40 stone steps	400
3420	Need 10 stone steps	Build 10 stone steps	100
3471	Need 18 stone steps	Build 18 stone steps	180
3772	Need start bog bridges		
3863	End need Bog Bridge	Install 12 bog bridges	72
4148	Need 18 stone steps	Build 18 stone steps	140
4269	Need 12 stone steps	Build 12 stone steps	120
	At Moosewood tree 8.5" DBH		
4349	False Trail		
4496	False Trail		
4510	Need 12 stone steps	Build 12 stone steps	120
4544	Need 30 stone steps	Build 30 stone steps	300
4600 027	<b>Jct Trail #1 and Trail #17</b>		
	<b>Return to Trail #15</b>		
6310 033	Nothern End of Trail 15		
6383	Stream crossing		
6976	Start need Bog Bridge		
7009	End need Bog Bridge	Install 4 bog bridges	32
7794 034	Jct Trail #15 and Trail #10		
	<b>Resume tour on 10/14/05</b>		
0	Jct Trail #10 and Ice Pond Road		
286	Jct Lighthouse Hill Road		
415	Jct Tribler @ School		
112 035	Jct Trail #6		
1183	No Smoking Sign		
1363	Connecting Tr to Norm Hill		
1594	Start need Bog Bridge		
1650	End need Bog Bridge	Install 7 bog bridges	56
	Alternate Step Stones		
1820	Start need Bog Bridge		
1919	End need Bog Bridge		
2005	Start improve sidehill		
2030	End improve sidehill	Improve 25 feet of sidehill tr.	20
2195	Start need Bog Bridge		
2317	End need Bog Bridge	Install 16 bog bridges	120
	Possible relocation uphill		

2617	036	Jct connector to #5		
		<b>Continue towards #7</b>		
2787		Spring in trail		
3175		Jct Trail #7 near Whitehead		
		<b>Return to conn.#5 via #7</b>		
		<b>Follow connector to #5 South</b>		
3737	036	Jct connector to #5		
3737		Start need Bog Bridge		
3793		End need Bog Bridge	Install 7 bog bridges	56
		Alternate Step Stones		
3874		Jct Trail 5		
		<b>Follow Trail 5 towards Whitehead</b>		
4035		Need waterbar	Build waterbar	12
4442	038	Jct Trail #1& 5@ Gull Cove		
		<b>Follow Trail #1 towards Whitehead</b>		
4525		False Trail to cove		
4555		Start need Bog Bridge		
4601		End need Bog Bridge	Install 6 bog bridges	48
4832		Need waterbar	Build waterbar	12
4843		Need 16 stone steps	Build 16 stone steps	160
4882		Need 8 Stone Steps	Build 8 stone steps	80
	039	Jct. Trail #1A		
		<b>Follow Trail #1 towards Whitehead</b>		
4964		Need 60 stone steps	Build 60 stone steps	600
5015		Need 14 stone steps	Build 14 stone steps	140
5074		Need 28 stone steps	Build 28 stone steps	280
		Need 2 waterbars	Build 2 waterbars	24
5214		Need 14 stone steps	Build 14 stone steps	140
6281		Need 16 stone steps	Build 16 stone steps	160
5488		Viewpoint		
5552		Fire Box Jct #7 and #1 on Whitehead		
		<b>Follow Trail #7 West</b>		
5580		Jct 1A and #7		
		<b>Follow 1A South to Gull Cove</b>		
5862		Need Stone Steps		
5897		End Stone Steps	Build 18 stone steps	180
5967	039	Jct #1 and #1A near Gull Cove		
		<b>Follow Trail 1 South</b>		
6414	038	Jct. #5 and #1		
6448		Stone Steps in place		
6480		Need Stone Steps		
6502		End Stone Steps	Build 12 stone steps	120
		Photo close to shore to Burnt Head		
7169		False Trail		
7190	042	Jct #1 and #1A near Burnt Head		
		<b>Follow Trail 1 South</b>		
7305		Need 16 stone steps	Build 16 stone steps	160
7368		Lifering		
7453		Need 50 stone steps	Build 50 stone steps	500
7473		Need 48 stone steps	Build 48 stone steps	480
7551		Viewpoint		
7623	043	Jct. #1 and #1A on Burnt Head		

	<b>Return North along 1A</b>		
	Steep, stable for now		
8003	Need 14 stone steps	Build 14 stone steps	140
	Need 18 stone steps	Build 18 stone steps	180
8077 042	Jct #1 and #1A near Burnt Head		
	<b>Travel south to Burnt Head</b>		
8598 043	Jct#1 and #1A on Burnt Head		
8598	Big Ledge, viewpoint		
8712 044	Jct. #4 and #1		
	Viewpoint		
	<b>Continue South on #1</b>		
8871	Need 30 stone steps	Build 30 stone steps	300
8947	Viewpoint		
8968 045	Jct.#1 Trail and #3 Trail		
	<b>Return to Trail #4</b>		
9041 044	Jct #4 and #1		
	<b>Follow Trail #4 West</b>		
9876	Trail sign please help near traps		
9900 046	Outward Bound trail to left		
	<b>Follow OB trail to #3</b>		
10204 047	Jct OB trail and Trail #3		
	<b>Return to #4</b>		
10515	Jct OB trail and Trail #4		
	<b>Resume West on #4</b>		
	Request gravel in muddy area		
10957	Sign, Jct Horn Hill Road		
11258 048	Rt. Spur off Horn Hill Road		
11402 049	Start Trail #5 to Gull Cove		
	<b>Follow #5 East</b>		
11707	Need start bog bridges		
11781	End need Bog Bridge	Install 10 bog bridges	80
12261	Need start bog bridges		
12340	End need Bog Bridge	Install 10 bog bridges	80
12705	Jct Trail #5 and Trail #6		
	<b>Return to Village</b>		
0 050	Start of Trail #3		
	<b>Follow Trail #3 East</b>		
25	Start need Bog Bridge		
275	End need Bog Bridge	Install 30 bog bridges	240
322	Need waterbar	Build waterbar	12
415	Need waterbar	Build waterbar	12
	Need start bog bridges		
494	End need Bog Bridge	Install 10 bog bridges	80
552	Need waterbar	Build waterbar	12
612	Macdonald trail		
959 047	Jct. Outward Bound Trail		
1772 045	Jct Trail #3 and #1 near Burnt Head		
	<b>Follow Trail #1 South</b>		
1837	Some soils washing diagonal		
1979	Need 10 stone steps	Build 10 stone steps	100
2026	Need 36 stone steps	Build 36 stone steps	360
2142	Need 10 stone steps	Build 10 stone steps	100

2187	Viewpoint		
2395	Viewpoint		
2473	Viewpoint		
2626	Need 16 stone steps	Build 16 stone steps	160
2696	Viewpoint		
2905	Viewpoint		
2937	Need 30 stone steps	Build 30 stone steps	300
2972	Start need Bog Bridge		
2999	End need Bog Bridge	Install 4 bog bridges	32
3119	Need 10 stone steps (with pins)	Build 10 stone steps	100
3181	Need 16 stone steps (with pins)	Build 10 stone steps	100
3253	051 Jct #1 and #1A		
	<b>Follow #1A South</b>		
3296	Start need Bog Bridge		
3420	End need Bog Bridge	Install 16 bog bridges	120
3928	Connector to #1		
3549	Connector to #1		
3874	052 Jct #1A and #1		
	<b>Walk back to 051</b>		
	<b>Follow Trail #1 South</b>		
3953	Need 10 stone steps	Build 10 stone steps	100
4070	Viewpoint		
4113	Viewpoint		
4124	Viewpoint		
4160	Connector to #1A at 3938		
4175	Start need Bog Bridge		
4200	End need Bog Bridge	Install 3 bog bridges	24
4214	Spring in trail		
	Viewpoint		
4391	Connector to #1A at 3549		
4513	Viewpoint		
4584	Viewpoint		
4617	Connector to #1A at 052		
	<b>Follow #1A SW</b>		
4769	053 Jct Trail #1 and #1A		
	<b>Walk back to near 052</b>		
4780	054 Connector on #1, next to 052		
	<b>Follow #1 Southwest</b>		
4855	On ledges, False Trail uphill		
4926	Need 12 stone steps		
4960	Jct #1 and #1A at 053		
4991	Viewpoint		
2993	False Trail (close)		
5022	Need 10 stone steps (with pins)	Build 10 stone steps	100
5077	Viewpoint		
5118	Viewpoint		
5162	Viewpoint		
5200	Viewpoint		
5249	Start need Bog Bridge		

5304	End need Bog Bridge	Install 7 bog bridges	56
5324	Start need Bog Bridge		
5373	End need Bog Bridge	Install 7 bog bridges	56
	Possible relocation uphill		
5447	Short cut trail		
5522	Life ring		
	Christmas Cove		
	Many trails		
5616	3 trails		
5695	3 trails		
5730	Many trails at Sheridan		
	Pick one trail and close others		
5789	3 trails		
5842	2 trails up ledge		
5875	Viewpoint		
5919	Viewpoint		
5971	6 trail to life ring 2 photos		
6070	Beach		
6209	Trail to Jamie Wyeth house		
055	Need 25 stone steps	Build 25 stone steps	250
	Rehab 3 trails	Rehab 3 trails	100
6335	Need 70 stone steps - 4 rocks wide	Build 70 stone steps	700
	Need simple signs		
	Need ropes and stones		
6424	Above Firebox		
6538	Need waterbar	Build waterbar	12
6622	Need waterbar	Build waterbar	12
6690	Need waterbar	Build waterbar	12
6751	Need waterbar	Build waterbar	12
6865	To Lobster Cove		
6928 056	Jct road to Lobster Cove		
7558 050	Jct Trail #3		
	Retrun to Village		
9792	At Library		
	<b>Walk out Trail #10 to Jct #1, near #14</b>		
12015	<b>Start Trail #1 going North</b>		
12145	Drain puddle		
	Need one bog bridge	Install 1 bog bridge	8
12412	Need 20 stone steps	Build 20 stone steps	200
12408	Old rip rap		
12497	Need 2 bog bridges	Install 2 bog bridges	16
12598	Need start bog bridges		
12672	End need Bog Bridge	Install 10 bog bridges	80
12812	Need 8 Stone Steps	Build 8 stone steps	80
12896	Need 1 bog bridge	Install 1 bog bridge	8
12984	Bridge is OK		
13007			
13043	Calf Cove		
13158	Viewpoint		
13739	Need 8 stone steps	Build 8 stone steps	80
13810	Small Seawall		
	Need 10 step stones	Build 10 stone steps	100

14545 Start need bog bridge  
14596 End need bog bridge  
14711 057 Jct #1A

Install 7 bog bridges

56

**Walk North on #1A**

14861 058 Jct #1A and #1

20204 = 84 weeks for MCC team at \$3500 per week = \$294,000
---

**Go back to 057**

**Follow Trail #1 NE**

14874 057

Native stone

0

14973 Viewpoint

14994 Rejoin #1A at 058

898 4"x8"x8ft Cedar

\$14,368

15263 032 Jct Trail #14 on North side of  
Island

300 4"-6"x8ft Cedar

\$2,700

400 lbs 3/8"x8" HDG spikes

\$320

059 Start of Trail #11

Materials Costs

\$17,388

Materials and transportaion costs may vary in your area.
---